

Volume Report

Project: D:\Raimundo\Desenhos Civil\Pref_Piranhas\Projetos Piau\Rua Maria Bernardino.dwg

Alignment: ALINHAMENTO Rua Maria Bernardino 02

Sample Line Group: SEÇÕES Rua M Bernardino 02

Start Sta: 0+000.000

End Sta: 0+133.000

<u>Station</u>	<u>Cut Area</u> <u>(Sq.m.)</u>	<u>Cut Volume</u> <u>(Cu.m.)</u>	<u>Reusable Volume</u> <u>(Cu.m.)</u>	<u>Fill Area</u> <u>(Sq.m.)</u>	<u>Fill Volume</u> <u>(Cu.m.)</u>	<u>Cum. Cut Vol.</u> <u>(Cu.m.)</u>	<u>Cum. Reusable Vol.</u> <u>(Cu.m.)</u>	<u>Cum. Fill Vol.</u> <u>(Cu.m.)</u>	<u>Cum. Net Vol.</u> <u>(Cu.m.)</u>
0+000.000	1.93	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
0+010.000	1.22	15.75	15.75	0.00	0.00	15.75	15.75	0.00	15.75
0+020.000	0.48	8.52	8.52	0.02	0.10	24.27	24.27	0.10	24.17
0+030.000	0.16	3.20	3.20	0.18	1.00	27.47	27.47	1.10	26.38
0+040.000	0.10	1.29	1.29	0.30	2.41	28.77	28.77	3.51	25.26
0+049.173	0.00	0.47	0.47	0.85	5.27	29.24	29.24	8.78	20.46
0+049.586	0.00	0.00	0.00	0.88	0.36	29.24	29.24	9.14	20.11
0+050.000	0.00	0.00	0.00	0.80	0.35	29.24	29.24	9.48	19.76
0+055.000	0.25	0.64	0.64	0.08	2.20	29.88	29.88	11.69	18.19
0+060.000	1.56	4.54	4.54	0.00	0.19	34.42	34.42	11.88	22.54
0+070.000	2.20	18.80	18.80	0.00	0.00	53.21	53.21	11.88	41.33
0+080.000	0.06	11.30	11.30	0.52	2.60	64.51	64.51	14.48	50.03
0+090.000	0.45	2.58	2.58	0.55	5.33	67.09	67.09	19.80	47.29
0+100.000	1.93	11.94	11.94	0.00	2.73	79.03	79.03	22.53	56.49
0+104.859	3.66	13.59	13.59	0.00	0.00	92.61	92.61	22.53	70.08
0+105.000	3.75	0.63	0.63	0.00	0.00	93.24	93.24	22.53	70.71
0+108.938	4.54	18.39	18.39	0.00	0.00	111.63	111.63	22.53	89.10
0+110.000	4.26	4.75	4.75	0.00	0.00	116.38	116.38	22.53	93.85
0+113.018	3.09	9.89	9.89	0.00	0.00	126.27	126.27	22.53	103.74
0+120.000	1.82	17.14	17.14	0.18	0.62	143.41	143.41	23.15	120.26
0+130.000	1.45	16.35	16.35	0.33	2.55	159.76	159.76	25.70	134.07
0+133.000	2.18	5.43	5.43	0.00	0.51	165.20	165.20	26.20	139.00